

**LARAMIE COUNTY COMMUNITY COLLEGE**  
1400 East College Drive, Cheyenne WY 82007

**ADDENDUM NO. 1**

**IFB No.:** IFB-16089  
**Description:** Auto Body Building – Paint Booth Replacement  
**Addenda Date:** December 7, 2015

---

***NOTE: Receipt of this Addendum must be acknowledged via this written instrument known as Addendum No. 1 and submitted with your Proposal/Bid. NO EXCEPTIONS.***

---

Participants are hereby notified that the aforementioned Bid has been revised and supplemented in accordance with this certain Addendum. Where provisions of this Addendum differ from those of the original Bid, this Addendum shall govern and take precedence. Applicants shall make all necessary adjustments to their proposal/bid submittals for revisions defined per this Addendum. This Addendum is hereby incorporated by reference and made a part of and condition of IFB-16047.

---

**SCOPE OF ADDENDUM**

Sign-in sheet from mandatory pre-bid meeting was emailed on December 2, 2015.

Addendum information:

1. Are OSHA training certifications required with bid? Yes, copies of the 10-hour cards for all Foremen that will be employed at the worksite, are required to be submitted with the bid.
2. Davis-Bacon Act information can be obtained at:
  - a. Information: [www.dol.gov/whd/govcontracts/dbra.htm](http://www.dol.gov/whd/govcontracts/dbra.htm)
  - b. Wage Rates: <http://www.wdol.gov/dba.aspx>
    - i. Select DBA WD by number: WY23
3. Construction documents were submitted to the Laramie County Building Department on December 3, 2015. The Plan Review portion of the permit application was paid. The successful contractor shall complete the application and pay the remaining permit fee as part of this contract.
4. Booth expected temperature maximum is 140 F. Fire sprinkler heads shall be selected with a temperature maximum of 180 F.
5. Portion of existing air compressed air line serving existing paint booth is subgrade. Demolish portion of exposed piping in existing pit. Abandon any piping encapsulated in slab. Cap and seal watertight pipe openings flush

with floor. New compressed air piping to be routed over paint booth with coordinated openings on east and west sides as per manufacturer's detail on the drawings. Support new piping from structure with drip legs on risers. Coordinate equipment to be provided by paint booth manufacturer.

**This Addendum consists of a total of two (2) pages and must be signed and submitted with your Proposal/bid.**

---

\_\_\_\_\_  
Authorized Signature for Company

\_\_\_\_\_  
Name of Company