

Addendum Number 2
Laramie County Community College
Arena Water Main Reconstruction
February 8, 2017

Addendum Number 2 applies to the above listed project.

Contractor questions and responses:

- a) The water main shall have restrained joints in addition to meeting BOPU standards (as per Addendum 1). Clarification: Joint restraints are not required for all water main joints, only joints that fall within the dimensioned proximity limits to tees, bends, deadends, etc. as called out on sheet N-2.
- b) Clarification: The requirement for granite aggregate is specific to crushed base course only. This is an owner requested item without appeal for substitution. Asphalt mix design can propose a substitution with the design submittal meeting the general specifications.
- c) Clarification: The Asphalt Patch bid item listed as (4"/8") references 4" asphalt over 8" inches of crushed base course. This section will be the standard asphalt section for the project.

Attachments: none.

Kelly W. Hafner

Kelly W. Hafner, P.E.
BenchMark Engineers, P.C.

Note: All bidders must acknowledge receipt of this addendum with the submittal of their bid.

END OF ADDENDUM 2