

SERVICES

Mechanical
Electrical
Plumbing
Fire Protection
Technology
Architectural Lighting
Commissioning

LOCATIONS

Cheyenne - WY
Denver Metro - CO
Boise - ID

ADDENDUM NO. 1

For

Owner: Laramie County Community College
Project Name: IFB-17169 Gas Meter Relocation
Project Address: 1400 E. College Dr.
CRA#: 2017-012
Date: April 11, 2017

ENGINEER:

Cator, Ruma & Associates, Co.
420 West Lincolnway
Cheyenne, WY 82001
(307) 274-3830

CONTACT	COMPANY	PHONE	EEmail
Cody Shaffer	Master Mechanical	(307) 388-0382	codyshaffer12984@hotmail.com
Tracy Roberts	Master Mechanical	(307) 363-3265	Mastermechanical78@hotmail.com

General Information:

- Add#1.1 Question: Is contractor paying fees for new meter or is LCCC?
Answer: The meter placement is already coordinated between LCCC and Black Hills Energy. LCCC will pay any fees if assessed.
- Add#1.2 Question: Does LCCC have a brand of regulator that you would like installed?
Example=Fisher.
Answer: No preference. Fisher is acceptable.
- Add#1.3 Question: Sod or seed for areas of excavation?
Answer: Sod for trenching wider than 5".
- Add#1.4 Question: Drawing M0.01. New building gas service tie in at fine arts building shows 2 1/2 riser. That will require welding or flanges. Can we sub and use a 2" Ips riser and go back up to 2 1/2 were the riser will be fused with 2x2 1/2 increase? Since all work on the meter will be 2" IPS NPT.
Answer: Underground piping is to be PE. Existing underground 2 1/2" is also PE.
- Add#1.5 Question: What certificate are you going to want see from welder?
Answer: Welder Performance Qualifications (WPQ) Certificate appropriate for the pressure vessel materials to be welded.

The preceding addendum shall be made a portion of the Contract Documents, and each bidder shall acknowledge receipt of the same in submitting bids. All other conditions and requirements of the Contract Documents will remain unchanged.

END OF ADDENDUM NO. 1

P:\Wyoming\LCCC\2017-012 Gas Meter Relocation\CA\Addenda\2017-012.adm1.20170411.docx