

LCCC – ALBANY COUNTY CAMPUS EMERGENCY GENERATOR ADDITION ADDENDUM #01 CRA# 2018-125 August 6, 2018

SPECIFICATIONS	
SPEC SECTION 26 32 14	
ADD.01-1	CLARIFY: Only Natural Gas Generator will be accepted for this design.
ELECTRICAL DRAWINGS	
SHEET G-1.1 - see attached full size sheet	
ADD.01-2	Updated panel schedules to reflect new lighting circuits. Lighting circuits shall be powered with (1) two pole 20A circuit breaker with shared neutral.
ADD.01-3	Added "Pipe Support Detail" for above ground piping between meter and generator.
SHEET G-1.2 - see attached full size sheet	
ADD.01-4	Updated Gas Equipment Connection Detail.
SHEET S-1.1 - see attached full size sheet	
ADD.01-5	Added meter location near generator.
ADD.01-6	Revised gas line from meter to generator.
ADD.01-7	Updated Keynote ES2, "Coordinate with utility company to provide dedicated meter for emergency generator to supply at 2 psig. Max Load: 850 CFH.
ADD.01-8	Updated Keynote ES10, "Extend 1 ½" G above grade and connect to generator. RE: Gas Equipment Connection Detail".
ADD.01-9	Added Keynote ES11, "Contractor to provide and install 14" W.C. regulator down stream of utility meter".
ADD.01-10	Updated circuit annotation for Battery Charger.
SHEET E-1.1 - see attached full size sheet	
ADD.01-11	Added existing lighting fixtures to plan.
ADD.01-12	Updated circuit annotation for lighting fixtures.
ADD.01-13	Updated Keynote E1, "Existing un-switched night lighting and corridor lighting circuits to be re-fed from new emergency power panel. Remove homerun wiring between panel and first luminaire. Make up wiring as required for feed through to balance of fixtures.
ADD.01-14	Updated Keynote E15, "Disconnect and remove all equipment associated with decommissioned wind turbine. Turn over all equipment to owner. <u>Equipment to be stored at Cheyenne campus.</u> Refer to one line for additional information.
ADD.01-15	Added suggested routing of conduit to first lighting fixture circuited to EME-12.
SHEET E-1.2 - see attached full size sheet	
ADD.01-16	Added existing lighting fixtures to plan.
ADD.01-17	Updated circuit annotation for lighting fixtures.
ADD.01-18	Updated Keynote E1.
ADD.01-19	Panel EMW relocated to north wall of Wiring Closet 207A.
ADD.01-20	Added suggested routing of conduit to first lighting fixture circuited to EMW-15.
ADD.01-21	Revised routing of conduit to first lighting fixture circuited to EMW-13.

SHEET E-2.1 – see attached full size sheet	
ADD.01-22	CLARIFY: Contractor will not be responsible for removing the existing wind turbine. All conductors have already been pulled out of existing raceways.

The preceding addendum shall be made a portion of the Contract Documents, and each bidder shall acknowledge receipt of the same in submitting bids. All other conditions and requirements of the Contract Documents will remain unchanged.

END OF ADDENDUM #01

CMI/___
P:\Wyoming\LCCC\2018-125 Generator Addition\CA\Addenda\2018-125_Add.01_20180806.docx